KOLAR DIVISION.

Dated 5th October 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 9th November 1929, for Restoring Ajjampalli Bidarekere, Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Ajjampalli, Bidarekere Tank" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenders must quote specific rates for all items both in words and in figures.

10. The tenders stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for Resorting Ajjampalli Bidarekere of Bowringpet Taluk (Revet R. L. 53·50 and bund R. L. 55·50.)

Sl. No.	Items of work	Unit of work	Approximate quantity
1	Earthwork to bund heating and tamping, etc., complete ...	C.yd.	2,834
2	Turfing	S.yd.	1,963
3	Removing and resetting old stone work	C.yd.	253
4	New stone work	,,	365
5	Grave stone figuring and painting, etc., complete	No.	10
6	Index stones do	,,	10
7	Reg. No. stone do	,,	1
8	B. M. stones do	,,	2
9	Gauge stone do	,,	1
10	Jungle clearing, grade	Grade	4
11	Cutting grips and trenches	,,	10
	Sluice.		
1	Earthwork excavation	C.yds.	57
2	Surki concrete	C.ft.	180
3	Burnt brick in surki mortar	,,	376
4	Burnt stone slabs 4" to 6" thick	S.ft.	128
5	Surki mortar plastering	Sqrs.	3·42
6	Cast iron pipe of 5" diameter	R.ft.	36
7	Providing wooden plug and rod and locking arrangements ...	Lump sum	
8	Cutting holes in orifice slabs	No.	2
	Waste weir.		
1	Earthwork excavation in chettu soil	C.yd.	63
2	Burnt brick in surki mortar	C.ft.	272
3	Burnt stone slabs 4" to 6" thick	S.ft.	170
4	Surki mortar plastering	Sqr.	2·62
5	New stone work	C.yd.	41
6	Removing and resetting old stone work with new jelly wherever necessary.	,,	16

Notice dated 5th October 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 9th November 1929, for Restoring *Balla* Agrahar tank, Mulbagal Taluk, Reg. No. 186. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 225 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Restoring Bellur Agrahar tank, Mulbagal Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tender must quote specific rates for all items both in words and figures.

10. The tenders stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for Restoring Balla Agrahara Tank, Avani Hobli, Mulbagal Taluk.

Sl. No.	Items of work	Unit of work	Quantity
	Bund.		
1	Earthwork to bund with watering and tamping	C.yd.	9,926
2	Turfing	S.yds.	5,750
3	Resetting old stone with new jelly	C.yd.	187
4	New stone pitching	S.yd.	1,014
5	Fixing grade stones with bed slabs including cutting figures and painting, etc., complete.	No.	18
6	Index stones with bed slabs including cutting figures and painting, etc., complete.	,,	18
7	B. M. stones with bed slabs including cutting figures and painting, etc., complete.	,,	2
8	R. No. stone with bed slabs including cutting figures and painting, etc., complete.	,,	1
9	Gauge stone with bed slabs including cutting figures and painting, etc., complete.	,,	1
	Sluice.		
1	Repairing the leaky sluice by cut opening the bund ...	Lump	sum
	Constructing the R. A. waste weir per 75' long at R. L. 50·00		
1	Earthwork excavation	C.yd.	103
2	Surki mortar concrete	C.ft.	275
3	Burnt brick in surki mortar	,,	734
4	Burnt stone slabs	S.ft.	354
5	Fixing joggles	No.	8
6	Surki mortar plastering	Sqr.	4·64
7	Rough stone work per apron	C.yd.	5·3

N. LAKSHMINARASIMHAIYA,
Executive Engineer.